



I.E.D. Installations Limited

Committed to
Service

LIVERPOOL JOHN MOORES UNIVERSITY

- Project Value: £63,000
- Project Type: LV Panel Replacement
- Project Aim: Electrical Upgrade
- Project Completion: September 2024

LIVERPOOL JOHN MOORES UNIVERSITY

The Harold Cohen Library is the University of Liverpool's library on the north part of the city centre campus. Its resources cater for students studying within the Faculty of Science & Engineering and the Faculty of Health & Life Sciences, which includes the medical, dental and veterinary science courses.

The Programme ran for 4 weeks for the Builders Works & Enabling Works then for the changeover we had Phased Coordinated Weekends agreed with the Building Managers to arrange, off site monitoring and security, standby power and temps, attendances for power on per department and building, re-testing off all the sub mains per department and building.

We had to coordinate the shutdown of each department and building whilst building alongside the new 3 Phase Section Board, whilst retain the supplies to all buildings throughout term time.

We coordinated directly with CWC Associates & LJMU to deliver:-

- ❑ New Containment Ladder Rack system.
- ❑ Logistic Coordinated for Delivery from roadside drop off to plant room through Library Basement with Shift and Loads with Logistical drops of the panel parts.
- ❑ Ground & Underground Service Surveys to transport the part panel into situe for Plantroom Build.
- ❑ Small Power & Lighting Amendments.
- ❑ Erect the panel adjacent to the plantroom prior to shut down and changeovers.
- ❑ Disconnect the outboard Sub Main Wiring and re-connect inline with the departments & buildings.
- ❑ New Data Point.
- ❑ Electrical Testing and Commissioning.

HAROLD COHEN LIBRARY





